



Date

June 23, 2022

Subject

City of Greenville
North Ohio Street Reconstruction
DAR-GRE-1909

Dear Prospective Bidder:

Enclosed please find Addendum No. 1 dated June 23, 2022.

Please acknowledge your receipt of this Addendum on page 1 of the Bid Form of Article 3.01 of your bid submittal.

If you have any questions, please contact us.

Sincerely,

A handwritten signature in purple ink that reads "Matthew J. Hoying".

Matt Hoying,
Project Manager

Enclosures: Addendum No. 1

W. Central Ohio/E. Indiana
440 E. Hoewisher Rd.
Sidney, OH 45365
937.497.0200 Phone

S. Ohio/N. Kentucky
8956 Glendale Milford Rd., Suite 1
Loveland, OH 45140
513.239.8554 Phone

www.CHOICEONEENGINEERING.com



City of Greenville

North Ohio Street Reconstruction

Greenville, Ohio

June 23, 2022

ADDENDUM No. 1

Engineers Estimate

The Engineers Estimate has been updated from \$1,362,253.25 to \$1,385,099.25.

Bidding Document

Bid Forms

Page 3-7, Article 5.01

Item No. 202 Pipe Removed quantity has been updated to 65 FT.

Item No. 202 Manhole Abandoned has been added to the plans with a quantity of 4 each.

Item No. 204 Subgrade Compaction quantity has been updated to 3559 S.Y.

Item No. 254 Pavement Planing, Asphalt Concrete quantity has been updated to 1862 S.Y.

Item No. 301 5" Asphalt Concrete Base, PG. 64-22 has been updated to Item No. 301 3" Asphalt Concrete Base, PG. 64-22 and the quantity has been updated to 150 C.Y.

Item No. 304 Aggregate Base quantity has been updated to 659 C.Y.

Item No. 407 Non-Tracking Tack Coat @ 0.09 GAL/S.Y. quantity has been updated to 658 Gal.

Item No. 411 4" Stabilized Crushed Aggregate quantity has been updated to 40 C.Y.

Item No. 441 1-3/4" Asphalt Concrete Intermediate Course, Type 2, (449) quantity has been updated to 99 C.Y.

Item No. 441 1-1/4" Asphalt Concrete Surface Course, Type 1, (449) quantity has been updated to 135 C.Y.

Item No. 609 Type 6 Barrier Curb has been added to the plans with a quantity of 1050 FT.

Item No. 609 Curb and Gutter, Replaced In-Kind quantity has been updated to 112 FT.

Item No. 611 4" Conduit, Type B, 707.45, Storm Repair has been added to the plans with a quantity of 50 FT.

Item No. 611 6" Conduit, Type B, 707.45, Storm Repair has been added to the plans with a quantity of 50 FT.

Item No. 611 8" Conduit, Type B, 707.45, Storm Repair has been added to the plans with a quantity of 50 FT.

Item No. 611 12" RCP Storm Sewer quantity has been updated to 171 FT.

Item No. 611 15" RCP Storm Sewer quantity has been updated to 49 FT.

Item No. 611 Catch Basin Type 1 quantity has been updated to 6 Each.

Item No. 611 Catch Basin Type 1A has been added to the plans with a quantity of 1 Each.

Item No. 611 Catch Basin 2-2B quantity has been updated to 1 Each.

Item No. 611 Type 3 Storm Manhole has been added to the plans with a quantity of 1 Each.

Item 613 Low Strength Mortar Backfill has been added to the plans with a quantity of 102 C.Y.

Item No. 638 4" PVC C-900 DR-18 Water Main quantity has been updated to 32 FT.

Item No. 638 6" PVC C-900 DR-18 Water Main quantity has been updated to 96 FT.

Item No. 638 8" PVC C-900 DR-18 Water Main quantity has been updated to 388 FT.

Item No. 638 16" PVC C-900 DR-18 Water Main quantity has been updated to 509 FT.

Item No. 638 16" Water Main, Directional Drilled quantity has been updated to 385 FT.

Item No. 638 6" Gate Valve and Valve Box has been added to the plans with a quantity of 1 Each.

Item No. 638 8" Gate Valve and Valve Box quantity has been updated to 5 Each.

Item No. 638 16" Gate Valve and Valve Box quantity has been updated to 6 Each.

Item No. 644 Channelizing Line, 8" quantity has been updated to 360 FT.

Item No. 644 Stop Line quantity has been updated to 138 FT.

Item No. 644 Lane Arrow quantity has been updated to 7 Each.

Item No. 659 Seeding and Mulching, Class 1, As Per Plan has been updated to 3000 S.Y.

Item Special Cut and Plug, Type 2, As Per Plan quantity has been updated to 6 Each.

Item Special Master Meter and Backflow Enclosure has been added to the plans with a quantity of 1 Lump Sum.

Item Special CIPP Lining of Existing 12" Sewer Line quantity has been updated to 401 F.T.

Item Special CIPP Lining of Existing 15" Sewer Line quantity has been updated to 87 F.T.

Item Special CIPP Lining of Existing 21" Sewer Line quantity has been removed from the plans.

Item Special CIPP Lining of Existing 24" Sewer Line quantity has been updated to 1078 F.T.

Item Special Sanitary Manhole Protective Lining System has been updated to 8 Each.

Plan Sheets

Typical Section

Sheet 2 of 41

Typical Section Item #12 has been updated from Item 617-4" Compacted Aggregate to Item 609-Type 6 Barrier Curb.

Typical Section

Sheet 3 of 41

Typical Section Item #4 Item 301-Asphalt Concrete Base, PG64-22 has been updated from 5" to 3".

Estimated Quantities

Sheet 12 of 41

The estimated quantities were updated to match the changes reflected on the bid tab.