

**IV) Environmental Commitments Made and Resources to be Avoided**

- These **MUST BE** incorporated into the Contract and discussed with the contractor prior to construction

Were any commitments made during the project development process? **Yes**      No

**Commitment:** If the construction of this project will result in the discharging of dredged and/or fill material into waters of the United States, including wetlands. Section 10 of the Rivers and Harbors Act of 1899 (Section 10) requires a DA permit be obtained for any work in, on, over or under a navigable water. A delineation should be conducted on the project site to determine the presence of waters of the United States (e.g. rivers, tributaries [perennial, intermittent and ephemeral], ditches, ponds, wetlands, impoundments).

**Disposition:** A plan note, or provision will be added to the contract documents to instruct the contractor.

**Commitment:** In the event earth disturbing activities are one acre or more, coverage under Ohio EPA's "General Storm Water Permit Associated with Construction Activities" is required.

**Disposition:** A plan note, or provision will be added to the contract documents to instruct the contractor.

**Commitment:** Idle equipment, petrochemicals and toxic/hazardous materials should not be stored in the floodplain or near any drainage ways, ditches or streams that could convey such materials to the Greenville Creek State Scenic River or any of its tributaries. Petrochemicals and toxic/hazardous materials should not be discharged into any state scenic river, their floodplains or any of their tributary drainage ways, ditches or streams. Refueling of equipment should not occur in floodplains or near any tributary drainage ways, ditches or streams.

**Disposition:** A plan note, or provision will be added to the contract documents to instruct the contractor.

**Commitment:** The permittee should develop a Spill Prevention Countermeasure and Contingency Plan (SPCC) in the event of a spill or break in an equipment hydraulic line, which may discharge into waters of the state. All spills must be reported to the Ohio Spill Line (1-800-282-9378) in accordance with OAC 3750.06.

**Disposition:** A plan note, or provision will be added to the contract documents to instruct the contractor.

**Commitment:** Any and all construction debris, earthen debris, excess asphalt or concrete, wood debris from clearing, excess fill material, material excavated from the trench bottom and trash should be disposed of at an approved upland site or land fill above 100-year flood elevations. Disposal of any such material in wetlands, floodplains, or within 1000 feet of state scenic rivers is prohibited.

**Disposition:** A plan note, or provision will be added to the contract documents to instruct the contractor.

**Commitment:** Indiana bat and northern long-eared habitat and surrounding trees should be saved whenever possible. Any tree removal proposed by the local sponsor must take place between October 1 and March 31.

**Disposition:** A plan note, or provision will be added to the contract documents to instruct the contractor.

**Commitment:**

**Disposition:**

**Commitment:**

**Disposition:**